

4-032038

12-29

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-20,694-0000

NW SW NE /4 SEC. 03, 09 S, 27 W
3630 feet from S section line
2310 feet from E section line

Operator license# 9067

Lease Mosier well # B-1

Operator: DaMar Resources, Inc.

County Sheridan

Address: P.O. Box 70
Hays, Kansas 67601

Well total depth 4065 feet ^{132.11}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 245 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 29 Month: December Year: 94

Plugging proposal received from: Dan Schippers

Company: DaMar Resources, Inc. Phone: _____

Were: Order 325 sxs. 60/40 pozmix - 10% gel - 13 sxs. gel - 600# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 11:00A.M., Day: 29, Month: December, Year: 94

Actual plugging report: 8 5/8" set @ 245' w/150 sxs. cwc. 5 1/2" set at 4056' w/165 sxs. Perfs. 3864' - 3991'. P.B.T.D. 4022'. Critical area control shots at 2250' and 1400'. Pumped down 8 5/8" - 50 sxs. cement blend w/100# hulls to Max. P.S.I. 150#. Close in P.S.I. 150#. Squeezed 5 1/2" w/50 sxs. cement blend w/300# hulls - 13 sxs. gel - 175 sxs. cement blend w/200# hulls to Max. P.S.I. 500#. Close in P.S.I. 150#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
1-11-95
JAN 11 1995

Remarks: Anhy. 2244' - 2277'.

Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 2653 GL

I did / did not observe the plugging. Carl Goodrow

(agent)

Form CP-2/3

INVOICED
DATE 1-11-95
INV. NO. 42063

TD