

4-032292

12-18

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-179-20,114-0001

NE NE SE /4 SEC. 11, 09, 28 W
2310 feet from S section line
330 feet from E section line

Operator license# 4767

Lease: Welch Well # 11

Operator: Ritchie Exploration, Inc.

County: Sheridan 133.28

Address: P.O. Box 783188
Wichita, Kansas 67278-3188

Well total depth 4101 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 271 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Express Well Service License# 6426

Address: Victoria, Kansas 67671

Company to plug at: Hour: P.M. Day: 18 Month: December Year: 1997

Plugging proposal received from: John Nienberger

Company: Ritchie Exploration, Inc. Phone: -

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Order work string.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:50 P.M., Day: 18 Month: December, Year: 1997

Actual plugging report: 8 5/8" set at 271' w/225 sxs cwc. 4 1/2" set at 4103' w/200 sxs.
D.V. Tool set at 1803' with 130 BBL. Chem Pac. Ran tubing to 3500'. Displaced 50 sxs cement
blend slurry with 200# hulls. Pulled tubing to 2500'. Displaced 50 sxs cement blend with
200# hulls. Pulled tubing to 1500' circulated with cement blend slurry with 100# hulls.
Tied onto 4 1/2". Squeezed with total 185 sxs with 500# hulls mixed into Max. P.S.I. 500#.
Held. Squeezed 8 5/8" with 65 sxs cement blend to Max. P.S.I. 500#. Held. Plug complete.

STATE OF KANSAS
1-7-98
JAN 7 1998

Remarks:
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED
JAN 08 1998

DATE

INV. NO. 49898