

4-032356

4-22

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-179-20,117-0000
7'SW C.of
NE NW SE /4 SEC. 11, 09, 28 W
2305 feet from S section line
1655 feet from E section line

Operator license# 4767

Lease: Welch "P" Well # 2

Operator: Ritchie Exploration, Inc.

County: Sheridan 133.45

Address: P.O. Box 783188
Wichita, Kansas 67278-3188

Well total depth 4106 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 271 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License#

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 22 Month: April Year: 1999

Plugging proposal received from: John Niernberger

Company: Ritchie Exploration, Inc. Phone:

Were: Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Order workstring. 3950' top fish.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:00 P.M., Day: 22 Month: April, Year: 1999

Actual plugging report: 8 5/8" set at 271' w/225 sxs cwc. 4 1/2" set at 4102' w/200 sxs.
D.V. set at 1820' w/105 bbl Kem Pac. PBD 4054'. Prod. Perfs 3830' - 4042'.
Critical area control shots at 2350' and 1950'. Ran tubing to 3950'. Loaded hole and
squeezed with 190 sxs cement blend with 500# hulls. Max. P.S.I. 800#. Squeezed 8 5/8" with
50 sxs to Max. P.S.I. 300#.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did[X] / did not[] observe the plugging.

Carl Goodrow
(agent)

Form CP-2/3

INVOICED

DATE 4-30-99

INV. NO. 60908

RECEIVED
STATE CORPORATION COMMISSION
4-28-99
APR 28 1999

CONSERVATION DIVISION
Wichita, Kansas