

15-179-20123-0001

4-19

4-032054

E-25,481

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 S. MARKET, ROOM #2078
WICHITA, KANSAS 67202

API number: 15- - 1968
NE SE SE /4 SEC. 11, 09 S, 28 W
990 feet from S section line
330 feet from E section line

Operator license# 4767 Lease Welch "P" well # 3

Operator: Ritchie Exploration, Inc. County Sheridan

Address: 125 N. Market Well total depth 4145 ^{134.71} feet
Suite #1000 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 277 feet

Aband. oil well , Gas well , Input well X, SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 19 Month: April Year: 95

Plugging proposal received from: John Neinberger

Company: Ritchie Exploration, Inc. Phone:

Were: Order 350 sxs. 60/40 pozmix - 10% gel - 600# hulls.

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 01 1995

5-1-95

CONSERVATION DIVISION

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[Wichita]

Completed: Hour: 4:20P.M., Day: 19, Month: April, Year: 95

Actual plugging report: 8 5/8" set at 277' w/225 sxs. cwc. 4 1/2" set at 4144' w/200 sxs. PBTB 4102'. Perfs 3906' - 4081'. D.V. set at 1832' w/190 sxs. to 1220' - ran 1" to 1220' - circulated with 285 sxs. Squeezed 8 5/8" with 15 sxs. to Max. P.S.I. 300#. Close in P.S.I. 300#. Squeezed 4 1/2" with 335 sxs. cement blend with 600# hulls mixed in to Max. P.S.I. 700#. Close in P.S.I. 100#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Any plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did[X] / did not[] observe the plugging. Carl Goodrow
(agent)

INVOICED
DATE 5-5-95
INV. NO. 42767

Handwritten initials