

4-032355

E-25,481

4-22

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-179-20,183-0001

SW NE SE /4 SEC. 11, 09, 28 W
1650 feet from S section line
990 feet from E section line

Operator license# 4767

Lease: Welch "P" Well # 5

Operator: Ritchie Exploration, Inc.

County: Sheridan 132.93

Address: P.O. Box 783188
Wichita, Kansas 67278-3188

Well total depth 4090 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 274 feet

Aband. oil well___, Gas well___, Input well X, SWD___, D & A___

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 22 Month: April Year: 1999

Plugging proposal received from: John Niernberger

Company: Ritchie Exploration, Inc. Phone: -

Were: Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:30 P.M., Day: 22 Month: April, Year: 1999

Actual plugging report: 8 5/8" set at 274' w/225 sxs cwc. 4 1/2" set at 4087' w/200 sxs.
D.V. set at 1800' w/450 sxs cwc. PBDT 4061'. Prod. Perfs 3824' - 4036'. Squeezed
4 1/2" with 200 sxs cement with #500 hulls mixed into Max. P.S.I. 800#. Test 8 5/8" to 300#.
Cement at surface.

Remarks:

Condition of casing(in hole): GOOD___ BAD___ Anhy.plug: YES X NO___

Bottom plug(in place): YES___, CALC___, NO___ Dakota plug: YES X, NO___

Plugged through TUBING___, CASING___ Elevation:___ GL

I did[X] / did not[] observe the plugging.

Carl Goodrow
(agent)

INVOICED
DATE 4-30-99
INV. NO. 60908

RECEIVED
STATE CORPORATION COMMISSION
428-99
APR 28 1999
CONSERVATION DIVISION
Wichita, Kansas

Form CP-2/3