

6 031502

2-25

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,124-0000

SE SW NE, SEC. 11, T 9 S, R 28 W/EX

2970 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30108

Lease Name Rogers E Well # 2

Operator: Sterling OI Co. Inc.

County Sheridan 132.92

Name & Address 112 S. Broadway

Well Total Depth 4090 feet

Sterling, Ks. 67579

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet ²³⁹ ~~288~~ KCC RT

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Services License Number _____

Address Oakley, Ks.

Company to plug at: Hour: PM Day: 25 Month: Feb. Year: 19 91

Plugging proposal received from Orville Monroe

(company name) Sterling Oil Co. (phone) _____

were: 8 5/8 set at ²³⁹ ~~288~~ w/175 sks cwc ^{KCC} 5 1/2 set at 40 ⁸ ~~79~~ w/200 sks. PBSD 4046.

Pf 3798 - 4015. Casing sq at 1860 w/100 sks. Shot holes at 1445 and 2200.

Ordered 400 sks 65/35 poz 8% gel, 500 lbs. hulls. B. J. Services. Hoxie Tank

Service water trucks. Ran shot line to 3800. Hole open to prod pf.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00PM Day: 25 Month: Feb. Year: 19 91

ACTUAL PLUGGING REPORT Sq 5 1/2 casing w/300 sks cement blend w/500 lbs.

hulls mixed into max psi 700 lbs. Close in psi 200 lbs. Sq 8 5/8 w/100 sks

cement blend to max psi 150 lbs. Close in psi 150 lbs. Plug complete.

RECEIVED STATE CORPORATION COMMISSION

3-13-91 MAR 13 1991

Remarks: (If additional description is necessary, use BACK of this form)

INVOLCED

(do not observe this plugging.)

DATE 3-15-91

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow

INV. NO. 31198