

6 031503

X 2-25

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 1579-20,129-0001 E-20,979  
NW SE NE SEC. 11, T 9 S, R 28 W/E<sup>x</sup>  
3630 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30108  
Operator: Sterling Oil Co. Inc.  
Name & Address 112 S. Broadway  
Sterling, Ks. 67579

Lease Name Rogers E Well # 3  
County Sheridan 132.60  
Well Total Depth 4080 feet  
Conductor Pipe: Size            feet  
Surface Casing: Size 8 5/8 feet 228

Abandoned Oil Well            Gas Well            Input Well xxx SWD Well xx D&A           

Other well as hereinafter indicated KCC CD 18231 KDHE C 20979

Plugging Contractor B. J. Services License Number           

Address Oakley, Ks.

Company to plug at: Hour: PM Day: 25 Month: Feb. Year: 19 91

Plugging proposal received from Orville Monroe

(company name) Sterling Oil Co. (phone)           

were: 8 5/8 set at 228 w/175 sks cwc. 5 1/2 set at 4079 w/200 sks. PBD 4038.

PF 3972 - 3999. SQ at 1915 w/150 sks. Shots at 1445 and 2200. Order 400 sks  
65/35 poz 8% gel 500 lbs. hulls. B. J. Services, Hoxie Tank Service water  
trucks. Ran shot line to 3800. Hole open to prod pf.

           Plugging Proposal Received by Carl Goodrow  
           (TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part            None           

Operations Completed: Hour: 4:15PM Day: 25 Month: Feb. Year: 19 91

ACTUAL PLUGGING REPORT Sq 5 1/2 w/300 sks cement blend w/500 lbs. mixed into max  
psi 700 lbs. Close in 300 lbs. Sq 8 5/8 w/100 sks cement blend to max  
psi 200 lbs. Close in psi 200 lbs. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
3-13-91  
MAR 13 1991  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks:           

**INVOICED** (if additional description is necessary, use BACK of this form.)  
I (did / did not) observe this plugging.

DATE 3-15-91  
INV. NO. 31197

*J.S.*

Signed Carl Goodrow  
(TECHNICIAN)

Carl Goodrow  
FORM CP-2/3  
Rev. 01-84