

To: **6 031058**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-179-20503-0000
4-7-88
450 R
API NUMBER 15- 1978

C SW SW, SEC. 22, T 9 S, R 29 W/E
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652

Lease Name Hughes Well # 1

Operator: Mustang Drilling and Exploration In County Sheridan 139.25

Name & Address P. O. Box 1609

Well Total Depth 4300 feet

Great Bend, Kansas 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 502

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing License Number 6050

Address Chase, Kansas

Company to plug at: Hour: _____ am Day: 7 Month: 4 Year: 19 88

Plugging proposal received from Ron

(company name) Kelso Casing (phone) _____

were: 8 5/8" set @ 502' w/ 350 sx. 5 1/2" set @ 4283' w/ 200sx. Top Perf 4150'. Order sand and common cmt. Pull pipe. Order 200 sx. ATL cement blend 65/35 pozmix, 10% gel, 2% dicel, 5 sx hulls.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None xxx

Operations Completed: Hour: 10:00 am Day: 7 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 4100i' w/5 sx common cmt on sand w/ bailer.

3 shots, recovered 1700' of 5 1/2" casing. Squeezed 8 5/8" w/ 25 sx cem blend followed w/ 175 sx cement blend w/ 5 sx hulls mixed in. To maximum psi 500#. Close in @ 300#.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-22-88

INV. NO. 20932

RECEIVED
STATE CORPORATION COMMISSION
JUN - 9 1988
6-9-88
CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow