

1-2 15-179-20483-0000 50
4-031665 R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -
C SW SE /4 SEC. 22, 09 S, 29 W
660 feet from S section line
1980 feet from E section line

Operator license# 4767 Lease Pratt Heirs well # P-1

Operator: Ritchie Exploration, Inc. County Sheridan

Address: 125 N. Market Well total depth 4250 feet ^{138.12}
Suite 1000 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 259 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: Chase, Kansas

Company to plug at: Hour: Day: 2 Month: March Year: 92
~~January~~

Plugging proposal received from: Mike

Company: Kelso Casing Pulling, Inc. Phone:

Were: Order sand and common cement. Pull pipe.

Order 250 sx. 65/35 pozmix - 10% gel. - Allied Cement Company.

Hole open to T.D. by bailer.

8 5/8" set @ 259' w/200 sx. 5 1/2" set @ 4250' w/200 sx.

P.B.T.D. 4215'. Perf. 3972' - 4160'.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:30 P.M., Day: 2, Month: March Year: 1992
~~January~~ ^{KCC RT}

Actual plugging report: Sand back to 3920' w/5 sx. common cement on sand with bailer. 2 shots recovered 1500' of 5 1/2" casing.

Mix and pump cement blend through 5 1/2" casing to 2100'. Lay down tubing. Tie on to 8 5/8" casing squeezed with total 250 sx. cement blend w/500# hulls mixed in to Max. P.S.I. 500#. Close in P.S.I. 200#. Plug complete.

RECEIVED
CONFIRMATION COMMISSION
MAR 15 1992
3-13-92
CONSERVATION DIVISION

Remarks:

Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO

Bottom plug(in place):YES , CALC , NO Dakota plug:YES , NO

Plugged through TUBING , CASING . Elevation: GL

I did X / did not observe the plugging. Carl Goodrow

DATE MAR 20 1992

INV. NO. 34798

(agent)
Form CP-2/3