

X

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20223-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 7-9S-28W
4980 feet from S Section Line, 5130 feet from E Section Line
Lease/Unit Name: SHAW Well Number: 2
County: SHERIDAN Total Vertical Depth: 2060 ²³²⁶ _{27KCC} feet
Conductor Pipe: Size _____ feet:
Surface Casing: Size _____ feet:
Production: Size 5.5 feet: 2326
Liner: Size _____ feet:

Operator License No.: 6009
Op Name: DOUBLE EAGLE EXPLORATION, INC.
Address: 800 W. 47TH STREET, STE 318
KANSAS CITY, MO 64112

Well Type: SWD UIC Docket No: D15204.0 Date/Time to Plug: 09/17/2001 9:00 AM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 4 yards Redi-Mix - 5 sxs common cement - 3000# sand - 42 gallons water per yard.
Ownership of this well was in dispute.
Owner of record - Double Eagle Exploration #6009.
Double Eagle sold well to Lloyd Drilling Company #3300 (Expired 02/28/00).
R.L. Hrbek plugged for equipment only.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/17/2001 11:00 AM KCC Agent: CARL GOODROW

Actual Plugging Report:
5' 1/2" set at 2326' and cemented to surface with 500 sxs.
Prod. Perfs 1950' - 2100'.
PBSD 2060'. Fluid level low.
Filled hole with 4 yards Redi-Mix to surface. 6 yards yield.
Plug complete.

Remarks:
Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

KANSAS CORPORATION COMMISSION
3-19-09
MAR 19 2009
RECEIVED

APR 25 2001

WELL LOG

Chief Drilling Co., Inc.
905 Century Plaza
Wichita, Kansas 67202

SHAW #2 (SWD)
Approx. W/2 NW NW NW
Sec. 7-9S-28W
Sheridan County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 7-22-69
Completed: 7-25-69

Casing Record: Set 2326' of 5 1/2" casing 1' off bottom.
Circ. w/500 sacks 50/50 Pozmix 6% Gel,
1% Calcium Chloride.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>FORMATION TOPS</u>
Surface sand & clay	0	40	Anhydrite 2307'
Shale & sand	40	1797	
Shale, sand, & shells	1797	1980	
Sand	1980	2095	
Red bed & shale	2095	2307	
Anhydrite	2307	2317	
Total depth	2327		

STATE OF KANSAS, COUNTY OF BARTON) ss::

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the approximate W/2 of the NW NW NW of Section 7-9S-28W, Sheridan County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.
Jim Robinson
Jim Robinson, Office Mgr.

sworn to before me this 30th day of July, 1969.

Betty Brandt
Betty Brandt, Notary Public



Expires:

RECEIVED
STATE CORPORATION COMMISSION

FEB 0 1969

CONSERVATION DIVISION
Wichita, Kansas