

6-20 19-3

To: 6 031558  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,428-0000  
50' N of C  
S/2 NE, SEC. 9, T 9 S, R 27 (W)

TECHNICIAN'S PLUGGING REPORT

3350 feet from S section line  
1320 feet from E section line

Operator License # 5146

Lease Name McFadden Well # 3

Operator: Rains & Williamson Oil Co. Inc.  
Name &

County Sheridan 131.56

Address 435 Page Ct.

Well Total Depth <sup>PSTD 12/2000</sup> 4048 feet

220 W. Douglas

Conductor Pipe: Size \_\_\_\_\_ feet

Wichita, Kansas 67202

Surface Casing: Size 8 5/8 feet 326'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton License Number \_\_\_\_\_

Address Oberlin, Kansas

Company to plug at: Hour: A.M. Day: 20 Month: 6 Year: 19 91

Plugging proposal received from A.D. Belt

(company name) Rains & Williamson (phone) \_\_\_\_\_

were: 8 5/8 set @ 326' w/225 sx. cwc 4 1/2 set @ 4104' w/150 sx. perfs. 4036' - 40'.

Order 350 sx. 65/35 poz. 10% gel. 1000# hulls. Halliburton Services.

Hoxie Tank Services Water. Rod's Tubbing pulled out w/whole open to perfs.

Perforated @ 1400' and 2300'.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:20 P. Day: 20 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT Squeezed 4 1/2 w/225 sx. cement blend w/500# hulls mixed in to

max. P.S.I. 300#. Close in P.S.I. 150#. Squeezed 8 5/8 w/100 sx. cement blend to

max P.S.I. 300#. Close in P.S.I. 150#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
7-22-91  
JUL 22 1991

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 8-6-91

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 32574