

4- 090498

10-29

37  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-179-21,056-0000  
100' N. of C.  
S2 NE NE /4 SEC. 23, 09 S, 26 W  
3400 <sup>4390</sup> feet from S section line  
660 <sup>RTK</sup> feet from E section line

Operator license# 9482

Lease Pfeifer well # 6

Operator: National Petroleum Reserves

County Sheridan

Address: 250 N. Rock Road #340  
Wichita, Kansas 67202  
316-681-3515

Well total depth 4170 feet <sup>135.53</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 278 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Emphasis Oil Operations License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 26 Month: October Year: 92

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations Phone: -

Were: Spot plugs through drill pipe with heavy mud between all plugs.

1st. plug @ 2315' w/25 sacks.

2nd. plug @ 1375' w/100 sacks.

3rd. plug @ 330' w/40 sacks.

4th. plug @ 40' w/10 sacks.

Rathole: 15 sacks.

Plugging Proposal Received by: Ed Schumacher

Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 4:00A.M., Day: 29, Month: October, Year: 92

Actual plugging report: Hole reported plugged as above.

Order 190 sx. 60/40 pozmix with 6% gel. and 1 sx. celloflake or flowcel.

RECEIVED  
STATE CORPORATION COMMISSION  
11-9-92  
NOV 9 1992

Remarks: Halliburton

Condition of casing(in hole): GOOD      BAD      Anhy. plug: YES X NO     

Bottom plug(in place): YES     , CALC     , NO X Dakota plug: YES X, NO     

Plugged through TUBING     , CASING     . Elevation: 2651 GL

I did[      ] / did not[ X ] observe the plugging. Ed Schumacher

DATE 11-23-92

INV. NO. 36856

(agent)