

6-100465

11-22

116
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,058-0000
^{24 CS-4-10-06}
S2 SW SE /4 SEC. 21, 09 S, 26 W
330 feet from S section line
1980 feet from E section line

Operator license# 09860 Lease Corke well # 1

Operator: Caster Resources, Inc. County Sheridan

Address: 1200 East 27th Well total depth 4160 feet ^{BS.20}
Suite C Conductor Pipe: inch @ feet
Hays, Kansas 67601 Surface pipe 8 5/8 Inch @ 246 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operationsny License# 08241

Address: Russell, Kansas 67665

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2280 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1365 feet " 100 " Mousehole: sacks

3rd plug @ 290 feet " 40 "

4th plug @ 40 feet " Wiper plug & 10 sx.

5th plug @ feet "

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:30 am, Day: 22, Month: November, Year: 1992

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2640 GL, Anhydrite depth: 2281 - 2323 feet
Anhy. plug: YES Dakota plug: YES Bottom hole plug in place: NO
Plugged through drill pipe: YES
Did NOT penetrate Arbuckle, cemented by Allied

RECEIVED
STATE CORPORATION COMMISSION
11-25-92
NOV 25 1992

I did / did not X observe the plugging.

David K. Wann
David K. Wann P.I.R.T. II
(agent)

INVOICED
DATE DEC 07 1992
INV. NO. 36979