

6 060456

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 195-21, 655-00-00

SE, SEC. 2, T. 11 S, R. 25 W1/4

1650 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6040

Lease Name Tidball Well # 1

Operator: Bankhoff Oil Co.

County Trego 130.95

Name & Address: Box 700657

Well Total Depth 4029 feet

Tulsa, Ok. 74170

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 275' w/180'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated

Plugging Contractor R. & C. Drilling Co. License Number 1828

Address Hays, Mo.

Company to plug at: Hour: 10:00PM Day: 30 Month: Jan Year: 19 85

Plugging proposal received from John Wase.

(company name) R. & C. Drilling Co. (phone) 262-2784

were: Order 180 sh 3/8 pos mix - 6 7/8 gal - 3 3/4 gal - 1 lb. Flo-let. & 8 5/8" plug.  
Spot w/ drill pipe w/ no less than 36 Vis mud. between all plug

Plugging Proposal Received by Pat G. Lohel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:00PM Day: 30 Month: Jan Year: 19 85

ACTUAL PLUGGING REPORT

1st plug C 2050' w/20 sh.  
2nd plug C 1100' w/100 sh w/1 sh Flo-let.  
3rd plug C 325' w/40 sh.  
4th plug - solid bridge of hulls & plug C 40' w/10 sh.  
10 sh in rat hole

RECEIVED  
STATE CORPORATION COMMISSION  
2-11-1985  
FEB 11 1985  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: By Allied  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-13-85

Signed Pat G. Lohel  
(TECHNICIAN)

INV. NO. 6949  
1-30

4  
2-8-84  
mjr