

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-195-21177-0000

NE SEC. 10, T11 S, R25 W/4

FEET FROM N/S SECTION LINE

FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 8170

LEASE NAME Gerstner WELL # 1

OPERATOR: Gnad Oil & Exp.

COUNTY Trego

NAME & ADDRESS 300 W. 39th.

WELL TOTAL DEPTH 4324 \$140.53 FEET

Hays Ks.

CONDUCTOR PIPE: SIZE FEET

SURFACE CASING: SIZE 8 5/8 FEET 318

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL (D&A)

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR Drilling Oil Inc. LICENSE NUMBER 5145

ADDRESS RR. 1 Victoria Ks.

COMPANY TO PLUG AT: HOUR: PM DAY: 24 MONTH: 7 YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM Everett Mickelson

(COMPANY NAME) Drilling Oil Inc. (PHONE) 913 735-2204

WERE: Order 195 cement 50/50 pozmix 6% Gel. 3% cal. cl.

1sx. hulls 1- 8 5/8 plug.

Heavy mud between all plugs

Pump cement down drill pipe

Elev. 2400 Anhydrite 2025-66 Arbuckle No.

Dakota 1600 PLUGGING PROPOSAL RECEIVED BY Dale F. Balthazor (TECHNICIAN)

800 = 1100

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 12:45 AM DAY: 25 MONTH: 7 YEAR: 1983

ACTUAL PLUGGING REPORT

1st. plug 25 SX @ 2040

2nd. plug 100 SX @ 1100

3rd. plug 40 SX @ 320. 1sx hulls push plug to 40'

4th plug 10 SX @ 40

10 SX rat hole

REMARKS: 10 SX mouse hole

Cementing Co. Sun

I (DID) (DID NOT) OBSERVE THIS PLUGGING.

RECEIVED STATE CORPORATION COMMISSION 8-8-1983 AUG 08 1983

INVOICED

SIGNED Dale F. Balthazor (TECHNICIAN)

DATE 8-12-83

CONSERVATION DIVISION Wichita, Kansas

INV. NO. 5139-W