

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25335-00-00  
Spot: SENE SW Sec/Twnshp/Rge: 7-12S-17W  
1489 feet from S Section Line, 2823 feet from E Section Line  
Lease Name: SEIB Well #: 1  
County: ELLIS Total Vertical Depth: 3740 feet

Operator License No.: 32639  
Op Name: CORAL PRODUCTION CORPORATION  
Address: 1600 STOUT ST STE 1500  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	275	0	160 SX
PROD	5.5	3738	0	200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/21/2009 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: TOM MAIER Company: CORAL PRODUCTION CORPORATI Phone: (303) 623-3573

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 4% gel - 500# hulls - 16 sxs gel spacer.  
Port collar at 1425' w/150 sxs 60/40 pozmix - 6% gel.  
CIBP 3680'.  
121.55

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/21/2009 10:00 AM KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Quality Oilwell Cementing pumped 60 sxs 60/40 pozmix - 4% gel with 200# hulls - followed with 15 sxs gel and 300# hulls - pumped 185 sxs 60/40 pozmix - 4% gel.  
Max. P.S.I. 400#. S.I.P. 50#. Backside with 5 sxs cement.  
Max. P.S.I. 500#. S.I.P. 500#.

**Perfs:**

Top	Bot	Thru	Comments
3700	3704		
3495	3510		
3488	3495		
3476	3478		
3340	3350		
3168	3178		

**INVOICED**  
DATE 5-6-09  
INV. NO. 2009061494

RECEIVED  
APR 22 2009

Remarks: QUALITY OILWELL CEMENTING COMPANY.

KCC WICHITA

Plugged through: CSG

District: 04

Signed *Richard Williams*  
(TECHNICIAN)

CM

Form CP-2/3

PKT

APR 21 2009

Handwritten notes: "10/10/04" and "B-1"

Handwritten notes: "10/10/04" and "B-1"

CORAL PRODUCTION CORP  
DENVER CO 80202

7-12S-17W  
1530' FSL & 2540' FWL, SEC

#1 SEIB

site 6-1/4 N & 1-3/4 W OF CATHERINE KS  
contr: MURFIN DRILLING #8  
geol: LARRY NICHOLSON  
fr date 07/16/2004

cy: ELLIS  
field: BEMIS-SHUTTS

API 15-051-25335

spc date 09/01/2004  
orig comp 09/10/2004  
card issued 04/25/2005  
last revised 04/25/2005


ELV: 2163 KB, 2158 GL LOG	depth/datum
tops.....	1390 +773
ANH.....	1437 +726
B/ANH.....	3138 -975
TOP.....	3340 -1177
PLATTSM.....	3375 -1212
HEEB.....	3393 -1230
TOR.....	3418 -1255
LANS.....	3655 -1492
BKC.....	3680 -1517
PBTD.....	3699 -1536
ARB.....	3740 -1577
LTD.....	3740 -1577
RTD.....	3740 -1577

IP status:  
OIL, P 8 BO & 22 BWPD, SHAW 3168-3178, LKC 3488-3492, 11/04/2004  
NOTE: CORRECTION 8/25/2004 - ORIG FR 1530' FSL & 2550' FWL; WAS #1 TERENCE BRAUN  
CSG: 8-5/8" 275 / 160 SX (ALT 2), 5-1/2" 3738 / 200 SX, PORT COLLAR AT 1425 / 150 SX  
COMMENT: MI & RURT 9/1/2004  
NO CORES  
DSTS TAKEN - DETAILS NA  
TRGT ZN: LKC, ARB (OIL), PTD 3550 (ARB), MICT - CO, PF (ARB) 3700-3704, W / 2 SPF, AC 500 GAL (MA), SWB LD, NON-COMMERCIAL, SET CIBP AT 3680, PF (LKC) 3476-3478, 3488-3495, 3495-3510, AC 250 GAL (MA), SWB LD, RE-AC 1000 GAL (20%), SWB LD, RE-AC 1000 GAL & 300# SALT

COPYRIGHT 2004  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)