

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-01210-00-00
Spot: SESWSE Sec/Twnshp/Rge: 1-25S-3E
318 feet from S Section Line, 1686 feet from E Section Line
Lease Name: HAL MOORE Well #: 2
County: BUTLER Total Vertical Depth: 2680 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 333 N PORTLAND AVE
OKLAHOMA CITY, OK 73107

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	12.5	40		
PROD	5.188	2677		50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2009 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY CO. Phone: (316) 321-0550

Proposed Plugging Method: AS PER KCC RULES & REGS

87.10

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/24/2009 4:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/TBG @ 2,603', CONSOLIDATED MIXED & PUMPED 50 SXS CLASS 1 4% CC W/FLAKES AND DISPLACED IN CASING. DUG OUT CELLER. TAGGED CEMENT @ 2,216'. SHOT SQUEEZE HOLES @ 250'. PLATED CASING TOGETHER, SWEDGED INTO 5-3/16" ESTABLISHED CIRCULATION, CONSOLIDATED MIXED AND PUMPED 363 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED BETWEEN 5-3/16" & 12" CASING AND ON BACKSIDE OF 12" CASING INSIDE CONDUCTOR PIPE. PLUG DOWN 4:30 P.M. 3-24-2009.

INVOICED
DATE 5-6-09
INV. NO. 2009061495


KANSAS CORPORATION COMMISSION
APR 16 2009
RECEIVED

Remarks: CONSOLIDATED CEMENT TICKET #20627.

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

JK

PKT