

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19500-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 1-25S-3E
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HAL MOORE Well #: 1
County: BUTLER Total Vertical Depth: 2410 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 333 N PORTLAND AVE
OKLAHOMA CITY, OK 73107

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	2478		50 SX
PROD	5.188	2704		50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/23/2009 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY Phone: (316) 321-0550

Proposed Plugging Method: AS PER KCC RULES & REGS

78.33

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/23/2009 1:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/TBG @ 2,603', CONSOLIDATED MIXED & PUMPED 55 SXS CLASS A 4% CC W/FLAKES AND DISPLACED IN CASING. DUG OUT CELLER. TAGGED CEMENT @ 2,129', SHOT SQUEEZE HOLES @ 250'. PLATED CASING TOGETHER, SWEDGED INTO 5-3/16" ESTABLISHED CIRCULATION, CONSOLIDATED MIXED AND PUMPED 183 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED BETWEEN 5-3/16" & 7" CASING AND ON BACKSIDE OF 7" CASING INSIDE CONDUCTOR PIPE. PLUG DOWN 1:00 P.M. 3-23-2009.

INVOICED
DATE 5-6-09
INV. NO. 2009061495

KANSAS CORPORATION COMMISSION

APR 16 2009

RECEIVED

Remarks: CONSOLIDATED CEMENT TICKET #20625.

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

JK

PKT