

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-21275-00-00  
Spot: NENWNE Sec/Twnshp/Rge: 36-31S-12W  
4964 feet from S Section Line, 1674 feet from E Section Line  
Lease Name: HOAGLAND Well #: 1  
County: BARBER Total Vertical Depth: 4450 feet

Operator License No.: 5316  
Op Name: FALCON EXPLORATION, INC.  
Address: 125 N MARKET STE 1252  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4300		WITH 2 SX CMT
CIBP		4370		
CIBP		4410		
SURF	8.625	204		WITH 200 SX CMT
PROD	4.5	4448	720	WITH 125 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/13/2009 1:45 PM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: CHUCK TONER Company: FALCON EXPLORATION Phone: (316) 262-1378

Proposed Plugging Method: CIBP @ 4300' & 2 SX CMT. PLUG AT 600' WITH 10 SX GEL - 50 SX CMT. PLUG AT 240' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

144.63

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/13/2009 3:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4300' & 2 SX CMT. SPOTTED PLUGS THROUGH TBG. 1ST PLUG AT 600' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 240' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4372	4374		
4371	4375		
4360	4370		

INVOICED  
DATE 5-6-09  
INV. NO. 2009061497

RECEIVED  
APR 22 2009

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED  
APR 17 2009

Signed

Richard M. Lacey

(TECHNICIAN)

KCC DODGE CITY

Form 68-27