

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21223-00-00
Spot: N2NWNW Sec/Twnshp/Rge: 14-14S-10W
330 feet from N Section Line, 660 feet from W Section Line
Lease Name: PTACEK Well #: 1-14
County: ELLSWORTH Total Vertical Depth: 3000 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2900		
SURF	8.625	428		225 SX
T1	2.375	2896		
PROD	5.5	2998	1400	300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/10/2009 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: PER KCC REGULATIONS
97.50

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 04/10/2009 6:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:
SAND PERFS TO 2800' AND CAP WITH 5 SX'S CEMENT. CUT CASING @ 1400' AND PULL TO 1200' AND PUMP 35 SX'S CEMENT. PULL CASING TO 900' AND PUMP 35 SX'S CEMENT. PULL CASING TO 480'. LET CEMENT SET FOR AWHILE AND TAG CEMENT @ 870' WITH SAND-LINE. CIRCULATE CEMENT TO SURFACE FROM 480'. PULL CASING ON OUT, CELLAR STAYED FULL. USED TOTAL OF 210 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
2927	2933	CSG	
2858	2874	CSG	

INVOICED
DATE 5-6-09
INV. NO. 2009061499
RECEIVED
APR 21 2009
KCC WICHITA

Remarks: 60-40 POZ-4% GEL. COPELAND TICKET #C35442.
Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

PKT