

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-22393-00-00  
Spot: SESENE Sec/Twnshp/Rge: 6-26S-5E  
2970 feet from S Section Line, 330 feet from E Section Line  
Lease Name: MARSH A Well #: 11  
County: BUTLER Total Vertical Depth: 2520 feet

Operator License No.: 32693  
Op Name: HAWKINS OIL, LLC  
Address: 427 S BOSTON AVE STE 915  
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	225		175 SX
PROD	4.5	2519		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/26/2009 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: HUNT HAWKINS Company: HAWKINS OIL LLC Phone: (918) 382-7743

Proposed Plugging Method: AS PER KCC RULES & REGS, PLUG BACK 50' ABOVE PERFS, AND PERF SQUEEZE HOLES @ 275', CIRCULATE CEMENT TO SURFACE.  
81-90

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE  
Date/Time Plugging Completed: 03/26/2009 11:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2,450', CONSOLIDATED OIL WELL MIXED & PUMPED 35 SXS CLASS A 3% CC CEMENT & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2,195'. PRESSURED CASING @ 150#, HELD OK. SHOT SQUEEZE HOLES @ 275'. SWEDGED INTO 4-1/2" CASING, CONSOLIDATED MIXED & PUMPED 126 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 11:00 A.M. 3/26/2009. CONSOLIDATED OIL WELL CEMENT TICKET #20561.

Perfs:

Top	Bot	Thru	Comments
2458	2464		
2445	2452		

**INVOICED**  
DATE 5-6-09  
INV. NO. 2009061500  
KANSAS CORPORATION COMMISSION  
**APR 16 2009**  
**RECEIVED**

Remarks: OLD PERFS WERE SQUEEZED FROM 2445'-2452'.

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

SK

PKT