

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-16375-00-00
Spot: S2S2NW Sec/Twnshp/Rge: 1-16S-14W
2310 feet from N Section Line, 1370 feet from W Section Line
Lease Name: SCHNEIDER B Well #: 11
County: BARTON Total Vertical Depth: 3294 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	657	0	175 SX
PROD	4.5	3278	0	100 SX

107.06

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/24/2008 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOM LARSON Company: LARSON ENGINEERING, INC. Phone: (620) 793-2168

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 06/26/2008 5:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

CO 4 1/2" casing to 3230'. Allied rigged up - spotted 7 sxs gel and 50 sxs cement with 100# hulls at 3230'.
Spotted 75 sxs cement at 1568' - spotted 50 sxs cement at 753' - circulated cement to surface.
Tried to pump down 8 5/8" - blew nipple off casing head.
Pumped 50 sxs cement down 4 1/2" casing - circulated cement out 8 5/8" x 4 1/2" annulus.
Plugged with 225 sxs 60/40 pozmix - 4% gel - 7sxs gel and 100# hulls.

Perfs:

Top	Bot	Thru	Comments
3278	3294		Arb-open hole

NVOICED

DATE 5-6-09
INV. NO. 2009061504

KANSAS CORPORATION COMMISSION
APR 16 2009
RECEIVED

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

Handwritten initials/signature

APR 15 2009