

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23140-00-00  
Spot: W2SE Sec/Twnshp/Rge: 10-14S-15W  
1320 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: POLCYN A Well #: 1  
County: RUSSELL Total Vertical Depth: 3257 feet

Operator License No.: 3842  
Op Name: LARSON ENGINEERING, INC. DBA LAR  
Address: 562 W STATE RD 4  
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3235		
SURF	8.625	248	0	150 SX
PROD	5.5	3254	0	200 SX

105.85

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/20/2009 2:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: THOMAS LARSON Company: LARSON OPERATING COMPANY Phone: (620) 793-2168

Proposed Plugging Method: Ordered 255 sxs 60/40 pozmix - 4% gel - 500# hulls - 12 sxs gel.  
P.C. 892' to surface with 165 sxs 60/40 pozmix.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/20/2009 3:00 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

Allied rigged to 5 1/2" casing - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls, followed with 12 sxs gel.  
Pumped 165 sxs 60/40 pozmix - 4% gel with 300# hulls mixed in.  
Max. P.S.I. 700#. S.I. P. 500#.  
Rigged to 8 5/8" - pumped 15 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.

**Perfs:**

Top	Bot	Thru	Comments
3253	3256		GORHAM SAND O
3109	3112		L-KC
3042	3046		L-KC "B"
2985	2989		TORONTO
2912	2916		PLATTS
2740	2744		TOPEKA

**INVOICED**

DATE 5-6-09  
INV. NO. 2009061504

RECEIVED  
APR 22 2009  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #37447.

Plugged through: CSG

District: 04

Signed [Signature]  
(TECHNICIAN)

CM

Form CP-2/3

APR 21 2009

PRT

replacement card

LARSON OPERATING CO  
OLMITZ KS 67564-8561

Property of Ks Corp Comm  
#1 POLCYN A

10-14S-15W  
C W/2 SE

site: 2-1/4 S & 2-1/2 E OF GORHAM KS

city: RUSSELL

API 15-167-23140

contr: VONFELDT DRILLING #1

field: GORHAM

geol: ROBERT STOLZLE


date 03/03/97

date 03/05/97

date 03/08/97

date 07/21/97

date 06/08/98



ELV: 1858 KB, 1853 GL LOG	depth/datum
tops.....	
GRDHAVEN.....	2414 - 556
*TARK SD.....	2426 - 568
STOT.....	2485 - 627
*TARK SD-2.....	2516 - 658
TARK LM.....	2538 - 680
*TARK SD-3.....	2622 - 764
*TARK SD-4.....	2650 - 792
HOW.....	2681 - 823
TOP.....	2740 - 882
PLATTSM.....	2914 - 1056
HEEB.....	2965 - 1107
*TOR.....	2985 - 1127
LANS.....	3020 - 1162

IP status:

OIL, GORHAM 3254-3257, 03/21/97

LANS B.....	3042 - 1184
LANS G.....	3110 - 1252
BKC.....	3218 - 1360
LTD.....	3253 - 1396
RTD.....	3254 - 1396
GORHAM SD.....	3256 - 1398
DDTD.....	3257 - 1399

\*SAMPLE TOP

INFO RELEASED: 6/8/98 - WAS OIL WELL - TEMP COMP

CSG: 8-5/8" 248 / 150 SX (ALT 2), 5-1/2" 3253.5 / 200 SX, MULTI STAGE COLLAR AT 892 / 105 SX

COPYRIGHT 1998  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)

LARSON OPERATING CO  
OLMITZ KS 67564-8561

10-14S-15W  
C W/2 SE

#1 POLCYN A

COMMENT: MIRT 3/4/97; OPTIONAL LOG TOP - LANS G PORO 3110 (-1252)  
 SHOWS: 2740-2746 (TOP LM, PNPT PORO, GD UNF STN, GSFO), 2752-2756 (TOP LM, INTRXLN  
 PORO, RR PC W/UNF STN, GD TO EXCLNT CUT & FLUOR), 2832-2840 (TOP LM, TR PR VUG  
 PORO, MOTT STN, GD TO EXCLNT CUT & FLUOR), 2930-2940 (PLATTSM LM, PNPT PORO, GD  
 STN, CUT & FLUOR), 2985-2995 (TOR LM, TR PNPT PORO, STN, EXCLNT CUT & FLUOR),  
 3042-3056 (LANS B LM, GD TO EXCLNT OOL & OCC VUG PORO, FR TO GD ODOR, LT STN ON  
 PORES, APP FLUSHED, FR TO WK CUT & FLUOR), 3034-3040 (LANS LM, TR FR TO PR PNPT  
 VUG PORO, LT STN, FR CUT & FLUOR, FR ODOR), 3154-3160 (LANS LM, PR MLDC VUG  
 PORO, BLEED OIL, GD TO EXCLNT CUT & FLUOR)  
 NO CORES OR DSTS  
 TRGT ZN: GORHAM SD (OIL), PTD 3250 (GORHAM), MICT - CO TO 3254, DD 3256.5 TD,  
 (GORHAM SD OH), SO, NAT, SET 2-7/8" TBG AT 3220, NO PKR, POP, P TR OIL & 209 BW/24  
 HRS, OIL WELL (POTENTIAL NOT RPTD), DOFP 3/21/97