

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-00289-00-00
Spot: SENE Sec/Twnshp/Rge: 28-20S-13W
4290 feet from S Section Line, 330 feet from E Section Line
Lease Name: SANDROCK UNIT Well #: 1
County: BARTON Total Vertical Depth: 3581 feet

Operator License No.: 3273
Op Name: LOEB, HERMAN L.
Address: PO BOX 524
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	221	0	w/unknown sxs cmt
PROD	5.5	3557	0	w/unknown sxs cmt

116.38

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/14/2009 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: GEORGE PAYNE Company: LOEB, HERMAN L. Phone: (618) 943-2227

Proposed Well had rods and tubing in hole when rig moved in to plug.
Plugging Tied to pull rods - they parted at 350'. Tried to pull tubing - it parted at 380'.
Method: Tried to fish rods and tubing - fished seven more rods and 90' of tubing.
Could not get any more rods or tubing out. Tried to mill - got outside tubing - got down to 472' with mills and drill bits.
Worked on well for one week. Decided to plug.
Ordered 300 sxs 60/40 pozmix - 4% gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/14/2009 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 470' - tied to tubing - pumped 110 sxs cement - circulated cement to surface.
Pulled tubing - tied to casing - dug out backside and opened surface pipe to check for cement when pumping on casing.
Pumped 240 sxs down casing and had no cement out backside.
Pressured casing to 350# P.S.I. Shut in.
Tied to backside and pressured to 500# P.S.I.
Backside full - had been squeezed.

Perfs:

INVOICED
DATE 5-6-09
INV. NO. 2009061505

RECEIVED
APR 22 2009
KCC WICHITA

Remarks: WELL ORIGINALLY KNOWN AS MORRISON #1. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

cm PKT

SCHERMERHORN OIL

#1

MORRISON

28-20-13W 52

S E NE NE

Contr.

BARTON

County

E 1889 RB

Comm.

Comp.

1-16-53

IP

316 BOPD

PERM POT

Tops	Depth	Datum
HEEB	3127	-1238
BR LM	3245	-1356
LANS	3258	-1369
CONG	3498	-1609
ARB	3556	-1667
TD	3581	-1692

Casing

8" 221

5" 3557

PERF 3411-16

PERF 3523-25

ACID 700

SAND ROCK SOUTH

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

28-20-13W 52
S E NE NE