

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21455-00-00
Spot: SESW Sec/Twnshp/Rge: 27-25S-20W
660 feet from S Section Line, 3300 feet from E Section Line
Lease Name: WETZEL R Well #: 1-27
County: EDWARDS Total Vertical Depth: 4775 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	292		WITH 200 SX CMT
PROD	4.5	4772	1380	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/14/2009 9:22 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVE OLLER Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4600' & 4 SX CMT. PLUG AT 1380' WITH 15 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50# HULLS & 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

155.19

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/14/2009 10:50 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 4600' & 4 SX CMT. 1ST PLUG AT 1380' WITH 15 SX GEL, 50# HULLS, & 50 SX CMT. 2ND PLUG AT 330' WITH 50# HULLS & 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4676	4690		

INVOICED
DATE 5-6-09
INV. NO. 2009061506

RECEIVED
APR 22 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED
APR 15 2009
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

Form CP-2/3

PKT