

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-21530-00-00  
Spot: SESESE Sec/Twnshp/Rge: 2-26S-19W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: WILLIAMS A Well #: 2-2  
County: EDWARDS Total Vertical Depth: 4732 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	316		WITH 275 SX CMT
PROD	4.5	4718	2620	WITH 125 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/16/2009 10:25 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 4670' & 4 SX CMT. PLUG AT 1250' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.  
153.79

Plugging Proposal Received By: LINDLEY REIMER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/16/2009 11:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4650' & 4 SX CMT WITH BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1250' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4718	4726	OH	

**INVOICED**  
DATE 5-6-09  
INV. NO. 2009061506  
  
**RECEIVED**  
APR 22 2009

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

KCC WICHITA

Plugged through: CSG

District: 01

**RECEIVED**  
APR 17 2009  
KCC DODGE CITY

Signed Richard W. Lacey  
(TECHNICIAN)

Form CP-20