

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-133-01710-00-00  
Spot: SWSENE Sec/Twnshp/Rge: 33-27S-19E  
2790 feet from S Section Line, 900 feet from E Section Line  
Lease Name: LYLE MEYER Well #: B-5  
County: NEOSHO Total Vertical Depth: 710 feet

Operator License No.: 32595  
Op Name: MSG RESOURCES INC.  
Address: 975 1400TH ST  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2	710		
SURF	8	20		20 is an estimate

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/31/2008 8:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: MICHAEL BROWN Company: MSG RESOURCES Phone: (620) 365-0638

Proposed Plugging Method: Run cement strings inside and outside of the production pipe to TD and pump full of cement.  
35.00

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE  
Date/Time Plugging Completed: 10/31/2008 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:  
A 1" cement string was lowered down the inside of the 2" production pipe to 700'. A 1" cement string was washed down the outside of the 2" production pipe to 575'. The well was then pumped full of cement from btm to top thru this cement string. A total of 171 sacks of portland cement were used to plug well.

Perfs:  
  
RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 15 2009  
CONSERVATION DIVISION  
WICHITA, KS  
  
RECEIVED  
KCC DISTRICT #3  
APR 9 2009 AMD  
CHANUTE, KS  
  
INVOICED  
DATE 5-6-09  
INV. NO. 200900150

Remarks:  
Plugged through: CSG

District: 03 Signed Alan Dunning (TECHNICIAN) PKT  
Form CP-2/3