

State of Kansas



15-195-20285-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
10-21-1974  
OCT 21 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Red Bishop of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: Rains and Williamson Oil Company, Incorporated,

Complete Address: 435 Page Court, 320 West Douglas, Wichita, Kansas.

Lease Name: Denning Well No. 1

Location: SE-SE-SE Sec. 24 Twp. 11 Rge. (E)(W) 24

County: Trego Total Depth 4040' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Bishop was instructed to plug the well as follows:

205'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 975' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

*N. L. Nichols*

Conservation Division Agent