



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: E. H. Adair & Lee Phillips,

Complete Address: Wichita, Kansas. Box 7011

Lease Name: Gerstner Well No. 1

Location: SW-SW-NE Sec. 21 Twp. 11 Rge. (E)(W) 25

County: Trego Total Depth 4048 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Cook was instructed to plug the well as follows:

215'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 1240'.

Circulate hole with heavy mud. Pull DP to 1440 and displace 100 Sx.  
cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP.  
pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
8-12-1968  
AUG 12 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

W. L. Nichols  
Conservation Division Agent