

State of Kansas



15-195-20195-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
9-21-1971
SEP 21 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Herren of H-30 Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Herren guarantees payment of the plugging fee.

Operator's full Name: Benjamin B. Tepper.

Complete Address: 420 South Dixie Highway, Coral Gables, Florida.

Lease Name: Dechant Well No. 1 *cc 106*

Location: NW-NE-SW Sec. 22 Twp. 11 Rge. (E)(W) 25

County: Trego Total Depth 4095' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Herren was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 900'.

Circulate hole with heavy mud. Pull DP to 1125' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

R. L. Nichols

Conservation Division Agent