

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Schankie Well Service, Inc. Address: 1006 SW Blvd, PO Box 397 Madison, KS 66860 Phone: (620) 437 2595 Operator License #: 6470 Type of Well: Oil Docket #: The plugging proposal was approved on: 7-31-08 by: Mike Heffern, Dist #3 Is ACO-1 filed? No If not, is well log attached? Yes Producing Formation(s): Bartlesville Depth to Top: 1902' Bottom: 1944' T.D. 1970'

API Number: 15-NA Lease Name: Nuessen Well Number: A8 Spot Location (QQQQ): SE - NW - NE - 4290 Feet from North / South Section Line 1650 Feet from East / West Section Line Sec. 31 Twp. 21 S. R. 12 East West County: Lyon Date Well Completed: 2-16-70 Plugging Commenced: 7-31-08 Plugging Completed: 7-31-08

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Contains data for 7" and 4 1/2" casing.


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Spot 15sk cement plug down 2 3/8" tubing @ 1870', Gel Spacer, Perforate @ 800', Spot 15sk cement plug @ 800', Gel Spacer, Perforate @ 150', Spot 30sk cement plug to surface

Name of Plugging Contractor: Schankie Well Service, Inc. License #: 6470 Address: 1006 SW Blvd, PO Box 397 Madison, KS 66860 Name of Party Responsible for Plugging Fees: Schankie Well Service, Inc. Madison, KS 66860 State of Kansas County, Greenwood, ss.

Randall Schankie, Secretary (Employee of Operator) or (Operator) on above-described well, being first sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature] (Address) PO Box 397 Madison, KS 66860



Subscribed and SWORN TO before me this 29th day of September, 2008. Carol R. Bolen My Commission Expires: 1-9-2009

RECEIVED NOV 17 2008 KCC WICHITA

MAY 9 1970

Mulssen # 8 "A"

31 21 12 E
SE NW NE

Well Log

1080 + with
Bart

Company: Mulssen Oil Co.

Farm: Mulssen

Well: 8A

Location: 31 21 12 E sec 31 21 12 E Lyon County Kansas

Commenced: 2/12/70

Completed: 2/16/70

Casing: 107 8 of 7" cemented with 60 sacks
1971 9 of 4 1/2" cemented with 100 sacks

Contractor: Jackson & Jacobson

Production: Pending

Total Depth: 1970

Shale	0	25
Lime	25	40
Shale & Lime	40	108
Lime & Shale	108	150
Shale & Lime	150	695
Shale &	695	824
Lime	824	828
Sand & Gravel	828	960
Lime	960	1088
Shale	1088	1150
Lime	1150	1389
Shale	1389	1410
Shale & Shells	1410	1895
Shale	1895	1907
Sand Oil	1907	1944
Shale	1944	1970

0' is 4' above ground level

RECEIVED
NOV 17 2008

KCC WICHITA

K. G. S. LIBRARY

ID# 48-1214033
 CID# 165290
 Shop # 620 437-2661
 Cellular # 620 437-7582
 Office # 316 685-5908
 Office Fax # 316-685-5926
 Shop Address: 3613A Y Road
 Madison, KS 66860

Hurricane Services, Inc.
 P.O. Box 782228
 Wichita, KS 67278-2228

Cement, Acid or Tools
 Service Ticket
 02640

DATE 7-31-08

COUNTY Lyon CITY _____

CHARGE TO Schankie Well Services, Inc
 ADDRESS P.O. Box 397 CITY Madison ST Ks ZIP 66860-0397
 LEASE & WELL NO. Muesseu # 8A CONTRACTOR C.O. Tools
 KIND OF JOB Plug To Abandon SEC. 31 TWP. 21s RNG. 12E
 DIR. TO LOC. 5 miles North of Town OLD NEW

Quantity	MATERIAL USED	Serv. Charge	
			700.00
60 SKs	60/40 Pozmix cement		522.00
205 lbs	Gel 4%		41.00
300 lbs	Gel Spacers (between Plugs)		60.00
	BULK CHARGE		
M/L	BULK TRK. MILES		200.00
	PUMP TRK. MILES (5 miles from Shop)		N/L
1	Rental on wire line (Checked Depth on M. Well 5 1/2" casing)		50.00
	PLUGS		
		5.8% SALES TAX	36.13
		TOTAL	1609.13

T.D. 1890'
 SIZE HOLE _____
 MAX. PRESS. _____
 PLUG DEPTH _____
 PLUG USED _____

CSG. SET AT _____ VOLUME _____
 TBG SET AT _____ VOLUME _____
 SIZE PIPE 4 1/2" casing
 PKER DEPTH _____
 TIME FINISHED _____

RECEIVED
 NOV 17 2008

REMARKS: Plug Through 2" Tubing > 4 1/2" casing Ref at 800' and 150' **KCC WICHITA**
Note! Set Gel Spacers between Plugs.
Spot 15 SK Plug at 1870'
15 SK Plug at 800'
30 SKs at 160' to Surface

EQUIPMENT USED

NAME <u>Kelly Kimberlin</u>	UNIT NO. <u>185</u>	NAME <u>Rodger #186</u>	UNIT NO. _____
<u>Brad Butler</u>	HSI REP.	<u>Witnessed by Cliff Schankie</u>	OWNER'S REP.

Precision Well Perforators
PO Box 401
Chanute, KS 66720

Date 7/31/2008
Invoice # 2390

Bill To
Schankie Well Service
Box 397
Madison, KS 66860

Ship To

P.O. #
Terms Net 30

Ship Date 7/31/2008
Due Date 8/30/2008
Other

Item	Description	Qty	Price	Amount
Perforation	Nuessan #8A 07/31/2008 Perforate Well at 800.0'		450.00	450.00
Perforation	at 150.0'		200.00	200.00
Perforation	So Well can be properly plugged with cement Nuessan #A-6 08/21/2008 Perforate Well at 150.0'		450.00	450.00
	So Well can be properly plugged with cement			

RECEIVED
NOV 17 2008
KCC WICHITA