

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Russell County, Sec. 19 Twp. 11S Rge. 14 xE/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines

1650' FSL & 990' FWL

Lease Owner Rains & Williamson Oil Co., Inc.

Lease Name Roda Well No. #1

Office Address 435 Page Court, 220 W. Douglas, Wichita, Ks.

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed 2-5-82 19

Application for plugging filed 2-4-82 19

Application for plugging approved 2-4-82 19

Plugging commenced 2-4-82 19

Plugging completed 2-5-82 19

Reason for abandonment of well or producing formation

Commercial quantities of oil not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck

Producing formation Depth to top Bottom Total Depth of Well 3480'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	245'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug @ 660' w/70 sx.

Plug @ 250' w/40 sx.

Plug @ 40' w/10 sx.

Rat Hole 10 sx.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Wilson Rains, President of Rains & Williamson Oil Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Wilson Rains

435 Page Court, 220 W. Douglas, Wichita, Ks. 67202

(Address)

February 12, 1982

Juanita M. Green Notary Public

RECEIVED
STATE CORPORATION COMMISSION
2-16-1982
FEB 16 1982

CONSERVATION DIVISION
Wichita, Kansas



DRILLER'S LOG

COMPANY: Rains & Williamson Oil Co., Inc.

SEC. 19 T. 11S R. 14W

LOC. 1650' FSL & 990' FWL

WELL NAME: Roda #1

COUNTY: Russell

RIG NO. #9

TOTAL DEPTH 3480'

ELEVATION 1844 GL 1849 K

COMMENCED: 1-26-82 COMPLETED: 2-5-82

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 245' w/200 sx. 60/40 poz., 3% cc., 2% gel.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Clay, Sand & Shale	250
Lime	593
Lime & Shale	905
Shale	945
Lime & Shale	1091
Shale & Lime	1320
Lime & Shale	1634
Shale & Lime	2890
Shale	2999
Lime & Shale	3084
Shale & Lime	3133
Lime	3208
Lime & Shale	3287
Shale & Lime	3390
Lime	3480
<u>ROTARY TOTAL DEPTH</u>	<u>3480</u>

RECEIVED
 STATE CORPORATION COMMISSION
 2-16-1982
 FEB 16 1982
 CONSERVATION DIV.
 Wichita Kans.

STATE OF Kansas)

COUNTY OF Sedgwick)


SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the

Roda #1 well.

Wilson Rains
 Wilson Rains



Subscribed and sworn to before me this 12 day of February, 1982.

My Appointment Expires:

10-4-83

Juanita M. Green
 Juanita M. Green