

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-195-20,828-00-00

RECEIVED  
11-15-2001  
NOV 15 2001

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME Uhrich

WELL NUMBER #1-20

2080 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 20 TWP. 11S RGE. 22 XEYor (W)

COUNTY Trego

Date Well Completed 10/15/81

Plugging Commenced 10/19/01

Plugging Completed 10/19/01

KCC WICHITA

LEASE OPERATOR Te-Pe Oil & Gas

ADDRESS P.O. Box 522, Canton, Ks 67428

PHONE# (620) 628-4428 OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/19/01 (date)

by District #4 (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Toronto-Marmaton Depth to Top 3592 Bottom 4027 T.D. 4040

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Toronto	Water & Oil	269	GL	8-5/8	269	0
Lansing KC	Water & Oil	4036	GL	4-1/2	4036	0
Marmaton	Water & Oil					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Mix 125 sacks of 60/40 pozmix, 10% gel with 300# of hulls and pump down 4-1/2" casing. Fillup casing from bottom @4027' to top of hole with cement and shut in with 200#. Pressure up on 4-1/2" X 8-5/8" annulus and found it full of cement.

Name of Plugging Contractor Northwest Well Service, Inc. License No. 31664

Address Box 159, Merino, Colorado 80741-0159

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Te-Pe Oil & Gas

STATE OF Kansas COUNTY OF McPherson, ss.


Terry P. Bandy

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Terry P. Bandy

(Address) P.O. Box 522, Canton, Ks 67428



SUBSCRIBED AND SWORN TO before me this 13th day of November XX 2001

Cynthia G. Reimer  
Notary Public

My Commission Expires: May 15, 2002

al