

15-195-21071-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,071-00-00

LEASE NAME Nilhas "B"

WELL NUMBER 3

2,970 Ft. from S Section Line

2,970 Ft. from E Section Line

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

SEC. 17 TWP. 11S RGE. 22 (E) or (W)

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000, Wichita, KS 67202 COUNTY Trego

PHONE#(316) 267-4375 OPERATORS LICENSE NO. 4767

Date Well Completed 10/11/82

Character of Well oil

Plugging Commenced 4/27/87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4/27/87

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District #6

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation L/KC & Marmaton Depth to Top 3472' Bottom 3830' T.D. 3915'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing/KC	Oil 3472-3708	Surf	166'	8-5/8"	166'	none
Marmaton	Oil 3795-3830	Surf	3915'	4-1/2"	3914'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Filled 4 1/2" casing from TD to surface with 135 sx ATL cement, 4 sacks hulls.

Pressured to 300#, closed in. Filled 8-5/8" - 4 1/2" annulus with 65 sacks ATL cement, 2 sacks hulls, pressured to 200#, shut in.

Orders by Dennis Hamel/Plainville.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. N/A

Address Box 31, Russell, KS 67672

STATE OF Kansas COUNTY OF Russell, ss.

Galen B. Babcock


(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Galen B. Babcock

(Address) 125 N. Market, #1000, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 28th day of April, 1987



Carolyn S. Holdeman

STATE CORPORATION COMMISSION

Commission Expires: January 16, 1991

APR 29 1987
4-29-1987
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 07-86

15-195-21071-00-00
WELL LOG

COMPANY A. Scott Ritchie

SEC. 17 T. 11S R. 22W
LOC. SE SE. NW

FARM Nilhas "B" NO. 3


RIG. NO. 21

TOTAL DEPTH 3915'

COUNTY Trego
KANSAS

COMM. 8-30-82

COMP. 9-6-82



CONTRACTOR Murfin Drilling Company

CASING

10 10
15 5-5/8" csg set @ 166' w/165 sx. Common Quickset SEVATION

12 5

13 4 1/2" csg set @ 3914' w/150 sx. 60-40 Poz., 10% salt, 5% gel PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Soil & Sand	110'
Shale	2305'
Shale & Lime	3497'
Lime	3554'
Lime & Shale	3683'
Lime	3685'
Lime & Shale	3915'