

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: K & N Petroleum, Inc.
Address: 1105 Walnut, Great Bend, KS 67530
Phone: (620) 793-6005 Operator License #: 3208
Type of Well: SWD EOR Docket #: E-26,569
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 02/22/09 (Date)
by: Bruce Rodie (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-19149-00-01
Lease Name: Musenberg A
Well Number: 3
Spot Location (QQQQ): SW - NE - SW -
1650' Feet from North / South Section Line
3630' 3840 Feet from East / West Section Line
Sec. 33 Twp. 18 S. R. 11 East West
County: Barton
Date Well Completed: January 1954
Plugging Commenced: 02/23/09
Plugging Completed: 02/23/09


Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	175'	8-5/8"	175'	0'
	Production	0'	3394'	5-1/2"	3394'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Rigged up on well. Perf @ 1550'-625'. Tallied in tubing w/ 15 sacks gel & 50 sacks 60/40 poz 4% gel and 100# hulls @ 3012'. Pull up to 1512'. Circulate to surface w/ 200 sacks 60/40 poz 4% gel & 300# hulls. Pull tubing. Tie into 5-1/2". Mix cement to squeeze & try to force out braden head - 30 sacks w/ no circulation. Shut in 300#. Tie onto braden head. Mix 30 sacks. Shut in 150#. Rigged down.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc. License #: 6901
Address: 1822 24th Street, Great Bend, KS 67530
Name of Party Responsible for Plugging Fees: K & N Petroleum, Inc. - Edward S. Nemnich
State of Kansas County, Barton, ss.
Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

KANSAS CORPORATION COMMISSION
MAR 10 2009
RECEIVED


KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/2010

(Signature) Edward S. Nemnich
(Address) 1105 Walnut, Great Bend, KS 67530

SUBSCRIBED and SWORN TO before me this 9 day of March, 20 09
Karen J. Mitchell My Commission Expires: 4/13/2010
Notary Public