

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas


15-195000429-00-00

WELL PLUGGING RECORD

Trego County, Sec. 30 Twp. 11 Rge. 22 (E) (W) 2/26/62
C-SWSE SWNE C3

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner National Drilling Company, Inc.
Lease Name Baker-Hixson Well No. 1
Office Address 531 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed May 31, 1962 19
Application for plugging filed May 31, 1962 19
Application for plugging approved May 31, 1962 19
Plugging commenced May 31, 1962 19
Plugging completed May 31, 1962 19
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4036 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	205'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug at 250' with 20 sacks, center plug at 180' with 15 sacks, top plug at 35' with 10 sacks.

RECEIVED
STATE CORPORATION COMMISSION
6-8-1962
JUN 8 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor National Drilling Company, Inc.
Address 531 Petroleum Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick SS. _____
Howard A. Stoskopf (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Howard A. Stoskopf
531 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of May, 19 62

My commission expires September 1, 1965

Cynthia K. Tegeler
Cynthia K. Tegeler Notary Public.

15-195-00429-00-00

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

12 1/2 KGS
2 1/2 SCC
for other company

COMPANY NATIONAL DRILLING CO

FARM BAKER HIXON NO. I

SEC. 30 T. II R. 22

LOC. ~~CSW SE~~
SWNE

SS 2/26/09
KCC

COUNTY TREGO

TOTAL DEPTH 4036

COMM. MAY 21 62


COMP. MAY 31 62

SHOT OR TREATED

CONTRACTOR

ISSUED

KANSAS



CASING

20 10
15 8 5/8 wk I50 sks 205'
12 6
13 5

ELEVATION 2298 DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 100 SHALE & SHELLS
- 205 BLUE SHALE
- 395 SHALE
- 1000 SHALE RED BEDS TO SAND
- 1500 SHALE SAND
- 1570 SHALE & SHELLS
- 1755 SAND & SHALE
- 1798 ANHY
- 1985 SHALE SHELLS
- 2200 SHALE & SHELLS
- 2295 LIME & SHALE
- 2525 LIME & SHALE
- 2705 SHALE & LIME
- 2850 SHALE & LIME
- 2980 LIME & SHALE
- 3080 LIME & SHALE
- 3265 LIME & SHALE
- 3440 LIME & SHALE
- 3500 LIME
- 3558 LIME
- 3572 LIME
- 3615 LIME
- 3630 LIME
- 3665 LIME
- 3725 LIME
- 3793 LIME
- 3875 LIME
- 3930 LIME
- 3936 LIME
- 3985 LIME & CHERT
- 4017 LIME & CHERT
- 4036 LIME T.D

RECEIVED
STATE CORPORATION COMMISSION

7-11-1962
JUL 11 1962

CONSERVATION DIVISION
Wichita, Kansas

I HEREBY CERTIFY THAT THIS IS A TRUE AND CORRECT LOG OF THE ABOVE DESCRIBED WELL AS SHOWN BY THE DRILLING REPORTS


NATIONAL DRILLING CO INC

Howard A. Stoskoff
HOWARD A STOSKOPF

STATE OF KANSAS)

SEDGWICK COUNTY)

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC, IN AND FOR SAID COUNTY AND STATE THIS 4 DAY OF JUNE 1962



Cyrene K Tegeler
CYRENE K TEGELER NOTARY PUBLIC

MY COMMISSION EXPIRES
SEPT, 1 1965