


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Trego County. Sec. 30 Twp. 11S Rge. (E) 22 (W)

Location as "NE/CNWxSWx" or footage from lines. C NW NW
Lease Owner Bergman Drilling, Inc.
Lease Name Hixson Well No. 1
Office Address 425 Union Center Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed April 14, 19 63
Application for plugging filed April 14, 19 63
Application for plugging approved April 14, 19 63
Plugging commenced April 14, 19 63
Plugging completed April 14, 19 63
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Depth to top Bottom Total Depth of Well 3960 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
clay, shale and shells		0	227	8-5/8"	227	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to bottom feet for each plug set.

First plug set at 540' cemented with 20 sacks cement.
Second plug set at 220 cemented with 20 sacks cement
3rd plug set at 40 feet cemented with 10 sacks.

RECEIVED
STATE CORPORATION COMMISSION
4-25-1963
APR 25 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bergman Drilling, Inc. 507
Address 425 Union Center Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Harold Bergman, Vice-President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Bergman
425 Union Center Building, Wichita 2, Kansas
(Address)

Subscribed and sworn to before me this 23rd day of April, 19 63

Notary Public. (Signature)

My commission expires August 2, 1966



15-195-0115-00-00

W E L L L O G

Bergman Drilling, Inc.
#1 Hixson = C NW NW
Section 30-11S-22W
Trego County, Kansas

Date Commenced: April 5, 1963
Date completed: April 14, 1963

Casing record: 8-5/8" set at 227' w/ 150 saks.

0	-	100	Clay	<u>Tops:</u>	
100	-	185	Blue Shale	Anhydrite	1780 (+555)
185	-	227	Shale and Shells	Heebner	3554 (-1219)
227	-	730	Shale and Shells	Toronto	3577 (-1242)
730	-	895	Shale and Shells	Lansing-Kansas City	3593 (-1258)
895	-	1125	Sand and Shale	Base Kansas City	3822 (-1487)
1125	-	1330	Shale and Shells	Marmaton	3840 (-1505)
1330	--	1780	Shale and Red Bed	Conglomerage	3934 (-1599)
1780	-	1800	Anhydrite		
1800	-	1835	Anhydrite		
1835	-	2025	Shale and Shells		
2025	-	2350	Shale and Shells		
2350	-	2500	Lime and Shale		
2500	-	2665	Lime and Shale		
2665	-	2825	Shale and Lime		
2825	-	2975	Lime and Shale		
2975	-	3050	Lime and Shale		
3050	-	3125	Shale and Lime		
3125	-	3220	Shale and Lime		
3220	-	3300	Lime and Shale		
3300	-	3425	Shale and Lime		
3425	-	3495	Lime and Shale		
3495	-	3535	Lime and Shale		
3535	-	3610	Lime and Shale		
3610	-	3661	Lime		
3661	-	3695	Lime		
3695	-	3734	Lime		
3734	-	3791	Lime		
3791	-	3840	Lime		
3840	-	3894	Lime		
3894	-	3944	Lime		
3944	-	3960	Cherty Lime		
3960			Rotary Total Depth		

RECEIVED
STATE CORPORATION COMMISSION
4-25-1963
APR 25 1963
CONSERVATION DIVISION
Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

I, do swear that the statements and matter herein contained are true to the best of my knowledge.

BERGMAN DRILLING, INC.


Harold Bergman

Harold Bergman

Subscribed and sworn to before me this 23rd day of April, 1963.

Norma J. Johnson

Notary Public



My commission expires:

August 2, 1966