

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-04874-00-01
Spot: NENENW Sec/Twnshp/Rge: 22-11S-18W
5011 feet from S Section Line, 2983 feet from E Section Line
Lease Name: M DEAN Well #: 1
County: ELLIS Total Vertical Depth: 3500 feet

Operator License No.: 5386
Op Name: PRODUCTION DRILLING, INC.
Address: PO BOX 680
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	4.5	910		
PROD	5.5	3500	0	w/unknown sxs cmt
SURF	8.625	215	0	w/unknown sxs cmt

Well Type: SWD UIC Docket No: D16031.0 Date/Time to Plug: 03/06/2009 1:00 PM
Plug Co. License No.: 5386 Plug Co. Name: PRODUCTION DRILLING, INC.
Proposal Rcvd. from: AVEN WEAVERLING Company: PRODUCTION DRILLING, INC. Phone: (785) 625-1189

Proposed Plugging Method: Ordered out 150 sxs 60/40 pozmix - 4% gel - 200# hulls.
Perfs 696' - 904'.

113.75

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/06/2009 2:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Quality Oilwell pumped 125 sxs 60/40 pozmix - 4% gel with 200# hulls.
Max. P.S.I. 500#. S.I.P. 300#.
5 1/2" and 4 1/2" backside full of cement.

INVOICED
DATE 3-31-09
INV. NO. 2009061371

RECEIVED
MAR 13 2009
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

MAR 09 2009

WICHITA
 1943
 1943

H H BLAIR & E WAKEFIELD #1 DEAN

22-11-18W
 NE NE NW

Contr. _____ ELLIS County

E 1927 Comm. 8-19-47 Comp. 10-17-47 IP 3000 BOPD
 ECHO

Tops	Depth	Datum
ANH	1205	
H3EB	3110	
LANS	3161	
CONG	3421	
SIMP	3442	
ARB	3462	
TD	3467	

Casing
 8" 198
 5" 3463
 2200' OIH/1 hr
 Swb 300 BO/5 hrs

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS