

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20777-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 35-21S-15W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: KELLER Well #: 1
County: PAWNEE Total Vertical Depth: 3918 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: 453 S WEBB RD STE 100
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3916	0	WITH 100 SX CMT
SURF	8.625	930		WITH 425 SX CMT

127.34

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/10/2009 8:30 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: LUKE DYKES Company: YOUNGER ENERGY Phone: (316) 681-2542

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/11/2009 11:25 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN TBG TO 3150' & PUMPED 60 BBL OF MUD & 50 SX CMT. PRESSURED 8 5/8" X 4 1/2" ANNULUS TO 500 PSIG. PERFORATE 4 1/2" @ 940'. RAN TBG TO 940' & PUMPED 125 SX CMT. LOST CIRCULATION. SDON. 3/11/09: TAGGED CMT AT 615' WITH TBG. PUMPED 30 SX CMT DOWN TBG CIRCULATING TO SURFACE. PULLED TBG & TOPPED OFF 4 1/2" WITH 10 SX CMT. PUMPED 20 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. MAXIMUM PRESSURE 500 PSIG. SHUT IN PRESSURE 400 PSIG.

Perfs:

Top	Bot	Thru	Comments
3916	3918	OH	

INVOICED
DATE 4-6-09
INV. NO. 2009061379

RECEIVED
MAR 13 2009

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

KCC WICHITA

Plugged through: TBG

District: 01

RECEIVED
MAR 12 2009
KCC DODGE CITY

Signed Richard W. Lacey
(TECHNICIAN)

Form CP-278

PKT