

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22952-00-00  
Spot: S2SWSE Sec/Twnshp/Rge: 8-33S-12W  
380 feet from S Section Line, 1860 feet from E Section Line  
Lease Name: SPRINGER/BARTHOLOW Well #: 1-8  
County: BARBER Total Vertical Depth: 4890 feet

Operator License No.: 5822  
Op Name: VAL ENERGY, INC.  
Address: 200 W DOUGLAS AVE STE 520  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4650		158.93
CIBP		4760		
PROD	5.5	4880	3000	WITH 150 SX CMT
SURF	8.625	314		WITH 250 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/24/2009 2:45 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4500' WITH 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 340' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/24/2009 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4450' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PLUG THROUGH CASING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4829	4834		
4808	4822		
4688	4692		
4552	4568		
4548	4549		

INVOICED  
DATE 4-3-09  
INV. NO. 200906137

RECEIVED  
MAR 13 2009

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

KCC WICHITA

Plugged through: CSG

District: 01

RECEIVED

MAR - 3 2009

KCC DODGE CITY

Signed

Stephany J. Puffer  
(TECHNICIAN)

Form CR-28

PLS