

15-195-21339-00-00

R

6 030631

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-21,339-00-00

SWNESE SEC. 19, T 11 S, R 23 (W) B

1650 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5198

Lease Name W. DENNING Well # 1

Operator: A SCOTT RITCHIE

County TREGO 141.38

Name & Address 125 N. MARKET, STE. 950

Well Total Depth 4350 feet

WICHITA, KS.

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 205'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS 67524

Company to plug at: Hour: PM Day: 26 Month: 12 Year: 19 85

Plugging proposal received from MIKE KELSO

(company name) KELSO CASING (phone) _____

were: 8 5/8 @ 205' w/180 4 1/2 @ 4246' w/150 SX. PBTD 4246 PERFS. 3949'-3951'

ORDER COM. CMT & SAND SHOOT & RECOVER PIPE ORDER 180 SX. 60/40 P02
6% GEL 3% CC 40 SX. GEL. 4 SX. HULLS, ALLIED CMT. CO. WELLBROCK
WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:15 PM Day: 26 Month: 12 Year: 19 85

ACTUAL PLUGGING REPORT Dump SAND ON PBTD TO 3900' SPOT 4 SX. COM. CMT ON
SAND w/BAILER SHOT & RECOVERED 3008' OF 4 1/2".

MIX. & Pump 3 SX. HULLS + 30 SX. GEL. 100 SX. CMT. MIX. + 1 SX. HULLS
10 SX. GEL. 80 SX. CMT MIX. MAX. PSI 1000# CLOSE IN PSI 400#

PLUG COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
1-8-1986
JAN 8 1986

Remarks: _____
(If additional description is necessary, use BACK of CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE JAN 10 1986

Signed Carl Goodrow
(TECHNICIAN)

61
1-6-85
mjs

INV. NO. 119117