

4-070120

9-11

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-195-01,332-0001

SW SW NE /4 SEC. 26, 11 S, 23 W  
2970 feet from S section line  
2310 feet from E section line

Operator license# 5663

Lease: Mona Well # 1 OWWO

Operator: Hess Oil Company

County: Trego 132.86

Address: P.O. Box 1009  
McPherson, Kansas 67460

Well total depth 4088 feet  
Conductor Pipe: 0 inch @ 0 sxs.  
Surface pipe 8 5/8 Inch @ 205 feet

ABAND. oil well, Gas well, Input well, SWD., D&A X

Plugging contractor: Mallard J.V., Inc. License# 4958

Address: 2080 E. Kansas Avenue - McPherson, Kansas 67460

Company to plug at: Hour: A.M. Day: 11 Month: September Year: 1998

Plugging proposal received from:

Company: Mallard J.V., Inc. Phone: 785-731-2869

Were: Ordered 225 sxs 60/40 pozmix - 6% gel - 1/4# floseal per sack - one 8 5/8" W.P.  
Spot plug through drill pipe with heavy drilling mud between all plugs.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 2:30 P.M. Day: 11, Month: September, Year: 1998

Actual plugging report:

- 1st Plug at 4060' w/25 sxs. - Arbuckle Top.
- 2nd Plug at 1837' w/ 25 sxs. - Anhy. 1815' - 1862'.
- 3rd Plug at 1018' w/100 sxs. Dakota Base.
- 4th Plug at 255' w/40 sxs. - Base surface pipe +50'.
- 5th Plug at 40' s/10 sxs - one 8 5/8" W.P.
- Rathole with 15 sxs. - Mousehole with 10 sxs.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: 2360 GL

I did [ ] / did not [ X ] observe the plugging.

Richard Williams  
(agent)

Form CP-2/3

RECEIVED  
KANSAS CORP COM  
1998 OCT -1  
10-1-1998  
D P: 29

RD

INVOICED

DATE 10-2-98  
51407