

15-195-22013-00-00

6 061846

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 195-22-013 - 00-00  
SE , SEC. 26 , T 11 S, R 23 W 7E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135  
Operator: John O. Farmer Inc.  
Name & Address: Box 352  
Russell, Ks. 67665

1650 feet from S section line  
990 feet from E section line  
Lease Name Buchholz Well # 1  
County Trego 125.78  
Well Total Depth 3870 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 211 w/140 sks

Abandoned Oil Well Gas Well Input Well SWD Well U&A x

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number

Address Russell, Ks. 67665

Company to plug at: Hour: 1:15 P.M. Day: 4 Month: May Year: 19 89

Plugging proposal received from Tom Alm

(company name) Emphasis Oil Oper (phone)

were: Order 190 sks 60/40 Poz 6% Gel 3% Cal Cl 1 sk F.C. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis mud between all plugs with good circulation and no fluid loss.

RECEIVED  
STATE CORPORATION COMMISSION

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 1:15 P.M. Day: 4 Month: May Year: 19 89

ACTUAL PLUGGING REPORT  
1st plug at 1850' w/20 sks  
2nd plug at 1025' w/100 sks 1 sk F.C.  
3rd plug at 275' w/40 sks  
4th plug at 40' w/10 sks  
10 sks in rathole  
10 sks in mousehole

Remarks: Allied Cement (If additional description is necessary, use BACK of this form.)

INVOICED

I (did not) observe this plugging.

DATE 5-12-89

Signed Gilbert G. Scheck (TECHNICIAN)

INV. NO. 24817