

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21497-00-00
Spot: E2NE Sec/Twnshp/Rge: 10-23S-10W
1400 feet from N Section Line, 580 feet from E Section Line
Lease Name: KEESLING Well #: 1-10
County: RENO Total Vertical Depth: 3875 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3790	1540	100 SX CMT.
SURF	8.625	220		200 SX CMT. <u>125.94</u>

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/19/2009 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK PERFS TO 3740, 5 SKS CMT. REC. PIPE, 35 SKS 1400', 35 SKS 900', CIRC CMT 270-0

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 03/19/2009 2:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3740', AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 1540' AND PULLED TO 1400', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 900', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 270', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

INVOICED
DATE 4-8-09
INV. NO. PKT


RECEIVED
KANSAS CORPORATION COMMISSION
APR 02 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING. 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

