

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20015-00-01
Spot: NWSEW Sec/Twnshp/Rge: 8-15S-12W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HERBER Well #: 2
County: RUSSELL Total Vertical Depth: 3322 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3316	0	w/100 sxs cmt
SURF	8.625	288	0	w/175 sxs cmt

107.97

Well Type: EOR UIC Docket No: E19073.1 Date/Time to Plug: 03/12/2009 10:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KEVIN AXELSON Company: MURFIN DRILLING CO., INC. Phone: (785) 483-4459

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls - 16 sxs gel. Perf at 800' - 1150'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/12/2009 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2702' - plugged pulled three joints - pumped 16 sxs gel and 50 sxs cement.
Pulled tubing to 1212' - pumped 110 sxs cement - circulated.
Pulled tubing out - filled casing with 20 sxs cement.
Hooked up to braden head - pumped 35 sxs cement.
Max. P.S.I. 100#.

Perfs:

RECEIVED
MAR 16 2009
KCC WICHITA

INVOICED
DATE 4-9-09
INV. NO. 2009061383

Remarks: ALLIED CEMENTING COMPANY-TICKET #307487.

Plugged through: TBG

District: 04

Signed Ray A Dinkel
(TECHNICIAN) CM

MAR 13 2009

AGT

THREE G OIL, INC #2 HERBER 8-15-12W
NW SE NW

Contr. H-30 DRLG, INC Cty. RUSSELL

Geol. Pool HERBER CONE

E. 1867 KB Cm. 2/23/67 Cp. 3/30/67 IP POT 108 BOPD/NW
NATL, ARB 3316-22

LOG Tops	Depth	Datum	Csg.
ANHY	778	+1089	API 15-167-20,015
B/ANHY	816	+1051	8" 288/175 SX; 5" 3316/100 SX;
TARK	2435	-568	DST 3052-75/40", 15'M, BHP 108-409
ELMONT	2499	-632	#/20", FP 23-39#;
HOW	2633	-766	DST 3100-16/90"; 600' GIP, 142'
IOP	2669	-802	G&OCM, BHP 374-373#/45", FP 37-
QH	2853	-1016	66#;
HEEB	2938	-1071	DST 3216-30/40", 20'M, BHP 890-870
TOR	2956	-1089	#/20", FP 23-29#;
DOUG	2972	-1105	DST 3294-3322/90", 545' GSY V SLI
BR LM	3026	-1159	MDY OIL, BHP 1000-988#/45", FP
LANS	3042	-1175	48-272#; TEMP 105;
BKC	3277	-1410	
ARB	3314	-1447	D CEM TO 3322 TD, FU 1750' CL OIL,
LTD	3322	-1455	/12 HRS, NATL, NO TST, RT&R.

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS