

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-20402-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 36-19S-1W  
2310 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: YOUNG Well #: 1  
County: MCPHERSON Total Vertical Depth: 2975 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2975		125 SX
SURF	8.625	208		125 SX <u>96.69</u>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/09/2009 9:00 AM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES Phone: (620) 654-7149

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFS AND CAP WITH 4 SX'S CEMENT. FILL HOLE WITH MUD. PUMP 35 SXS AT 450'. CIRCULATE TO SURFACE FROM 260'.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/09/2009 2:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 2845' AND CAPPED WITH 4 SX CEMENT. CUT PIPE AT 602' AND PULLED. RAN TUBING TO 460' AND PUMPED 195 SX TO CIRCULATE TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2902	2907		

**INVOICED**  
DATE 4-9-09  
INV. NO. 2009061381

**RECEIVED**  
**MAR 16 2009**  
**KCC WICHITA**

Remarks: COPELAND CEMENTING #C-33865 TOTAL = 195 SX 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed Greg Eves  
(TECHNICIAN)

✓

PET