

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20250-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 16-18S-10W
2948 feet from S Section Line, 4910 feet from E Section Line
Lease Name: OBERLE Well #: 1
County: RICE Total Vertical Depth: 3295 feet

Operator License No.: 6901
Op Name: D S & W WELL SERVICING, INC.
Address: 1822 24TH STREET
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3295		
SURF	8.625	245		200 SX <u>107.09</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/02/2009 11:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: D S & W WELL SERVICING INC Phone: (620) 786-4258

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2009 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 2970' AND CAP WITH 5 SX'S CEMENT. ATTEMPT TO PULL CASING-CASING PARTED 15' BELOW SURFACE, DECIDED TO PERFORATE AND RUN TUBING. PERFORATE AT 1200', 900' AND 300'. RUN TUBING TO 1200' AND BEGAN PUMPING WITH 15 SX'S GEL FOLLOWED BY 35 SX'S CEMENT. PULL TUBING TO 900' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS. PULL TUBING TO 300' AND CIRCUALTE CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3182	3186	CSG	
3166	3174	CSG	
3115	3120	CSG	
3082	3185	CSG	
3012	3015	CSG	
3006	3008	CSG	

INVOICED
DATE 4-9-09
INV. NO. 2009061382
RECEIVED
MAR 17 2009
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. LOG TECH #5660. COPELAND TICKET C 33124.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

SK *PKT*