

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- \_\_\_\_\_

17-SE-SE, Sec. 32, T 11 S, R 23 W/E

\_\_\_\_\_ feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

\_\_\_\_\_ feet from W/E section line

Operator License # 5242

Lease Name Lame Well # 1

Operator: Petroleum Management Inc.  
Name & Address: 400 N. Woodlawn  
Suite 200  
Wichita, Kansas 67208

County Wago

Well Total Depth 4270 feet \$138.78

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8" feet 333' w/175' ex

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing License Number \_\_\_\_\_

Address Chase, Kansas

Company to plug at: Hour: 3:30 PM Day: 11 Month: 11 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Millard Kelso

(company name) Kelso Casing (phone) \_\_\_\_\_

were: 4 1/2" @ 4218' w/225' sy P.B. 4261'

Top Perf #2 4124' - P.B. w/4' sy cmt -> sand to

4100' -> 4' sy. cmt. - Recovered 3013' of 4 1/2" csg.

Ordered 190 sy 50' poz 6% gel - 25 sy gel - 6 hulls.

Signed Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 PM Day: 11 Month: 11 Year: 1983

ACTUAL PLUGGING REPORT Hooked-up to 8 5/8" S.P. - pumped in ->

2 hulls -> Release flag -> 3 gel w/hulls -> 50 cmt. w/hulls ->

10 gel w/hulls -> 70 cmt. w/hulls -> 12 gel w/hulls ->

70 cmt. May P.S.I. 600<sup>+</sup> Shut-in P.S.I. 200<sup>+</sup>

Flag was pumped to 1246' - flag moved evenly down  
hole with exception @ 800'-900' where flag app stopped briefly  
at different intervals before continuing down hole.

Remarks: El. 2395 - Anhy 1918'

*Pumped  
Flag*

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION  
12-5-1983  
DEC 5 1983

Signed Dennis L. Hamel  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

DATE 12-29-83

INV NO. 7279-W

CONSERVATION DIVISION  
Wichita, Kansas