

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-21350-00-00

SE, Sec. 35, T 11 S, R 23 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7027

Lease Name Rhoades Well # 1

Operator: Damar Oil Opp.
Name &
Address Hays Ks.

County Trego

Well Total Depth 4090 feet \$132.93

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drig. License Number 5422

Address 801 Union Ctr Wichita Ks. 67202

Company to plug at: Hour: AM Day: 29 Month: 10 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Dennis Sporing

(company name) Abercrombie Drig. (phone) 913-743-6777

were: order 185 sx cem 50/50 pozmix 690 gal. 390 c.c.

1sx hulls- 1 sx Flow Seal 1.8 5/8 plug.

Heavy mud between all plugs.

pump cem. down drill pipe.

Elev. 2435 Anhydrite 1887-1904 Arbuckle No.

Dakota 1700

735 = 1035

Signed Dale F. Balthazor
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None (None)

Operations Completed: Hour: 3:15 AM Day: 29 Month: 10 Year: 1983

ACTUAL PLUGGING REPORT

25 sx @ 1890

100 sx @ 1035 mixed with 1sx Flow seal


40 sx @ 300. 1sx hulls. push plug to 40'

10 sx @ 40

10 sx in Rat hole.

Remarks: _____

cementing w. Allied



I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED
DATE 11-8-83
INV. NO. 6043-W

Signed Dale F. Balthazor
(TECHNICIAN)