

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-115-20189-00-01  
Spot: NWNWSW Sec/Twnshp/Rge: 27-19S-1E  
2253 feet from S Section Line, 5073 feet from E Section Line  
Lease Name: FINCH KLASSEN Well #: 1  
County: MARION Total Vertical Depth: 2890 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2890		50 SX
SURF	8.625	153		100 SX

93.93

Well Type: SWD UIC Docket No: D25139.0 Date/Time to Plug: 03/03/2009 10:00 AM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Revd. from: DOUG WARD Company: AMERICAN ENERGIES Phone: (316) 263-5399

Proposed Plugging Method: RUN TUBING TO BOTTOM AND PUMP 35 SXS CEMENT. PULL TUBING TO 250' AND CIRCULATE TO SURFACE. RUN 1" TUBING DOWN BACKSIDE OF 5 1/2" TO 250' AND CIRCULATE TO SURFACE.

Plugging Proposal Received By: GREG EVES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/03/2009 10:00 AM KCC Agent: GREG EVES

Actual Plugging Report:  
RUN TUBING TO 2660' AND PUMPED 35 SXS TAGGED CEMENT AT 2240'. PULLED TUBING TO 255' AND PUMPED 35 SX'S TO CIRCULATE TO SURFACE. RAN 1" TUBING DOWN BACKSIDE 80' AND PUMPED 10 SXS TO CIRCULATE TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2801	2848		

INVOICED

DATE 4-15-09  
INV. NO. 2009061389

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 26 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND CEMENTING TICKET #33863 TOTAL = 80 SXS 60/40 POZ 4% GEL  
Plugged through: TBG

District: 02 Signed Greg Eves (TECHNICIAN)

*JK*

*AK*